SHIMOGA DIVISION.

Abstract Notification dated 14th February 1939.

The attention of the public is drawn to the Notification advertised in the *Mysore Gazette*, pages 121 to 123, Part VI, dated 19th January 1939, for constructing a Town Hall at Sorab, Shimoga District. The last date for receiving tenders has been extended till 4th of March 1939.

Notification dated 14th February 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 12th March 1939, for constructing compound wall and repairs to Sri Rameswaraswami Temple and other allied temples at Tirthahalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1939.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for (Rs. 217) rupees two hundred and seventeen for having credited the earnest money, to "17 (*a*) P. W. Deposits" and be superscribed "Tender for constructing compound wall and repairs to Sri Rameswaraswami Temple and other allied temples at Tirthahalli," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The successful tenderer will have to deposit another sum of Rs. 217 towards the security deposit before the execution of contract agreement.

14. Cement will be supplied by the department and only labour charges should be quoted.

Abstract estimate for constructing compound wall and repairs to Sri Rameswaraswami Temple and other allied temples at Tirthahalli.

No.	Items of work	Unit	Rate	Quantity	Cost
	I. Constructing Compound wall alround temple premises.		Rs. a. p.		Rs
1	Constructing compound wall with size stone in mud including excavating in foundation filling in foundations, basement slabs, parapets, pillasters and cement concrete coping slabs with cement pointing, etc., complete	R.ft.	1 14 0	445	
2	Providing gate pillars at the entrance 8' high ..	No.	29 0 0	2	
3	Providing and fixing iron gate, etc., complete as per design	L. S.	..	..	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
4	Providing and fixing kerb stones	Each	0 8 0	22	
5	Removing existing steps between Aswathakatte	S.ft.	0 1 0	49	
6	Earthwork excavating and forming ramp	C.yd.	0 4 0	73	
7	Rough stone work	,,	2 8 0	37	
8	Earthwork levelling ground and forming including removing stones, etc.	,,	0 2 6	500	
9	Reconstructng ½ old and ½ new stones revetment	L. S.	..	..	
	II. Repairs to Sri Rameswara and Sureswara Temples.				
1	Dismantling laterite brick compound wall	C.ft.	0 0 3	3,580	
2	Earthwork removing platform	C.yd.	0 4 0	16	
3	Dismantling stone in mud with slabs	C.ft.	0 0 4	133	
4	Constructing compound wall with available laterite brick in mud	,,	0 1 6	664	
5	Levelling platforms	C.yd.	0 2 6	7	
6	Removing boulders by blasting	,,	2 0 0	37	
7	Constructing steps	Each	10 0 0	2	
8	Cement concrete 1 : 2 : 4 to stop leaks	C.ft.	0 10 0	194	
9	Cement plastering ¾″ thick 1 : 3	Sqr.	9 0 0	5·81	
10	Cement pointing	,,	4 0 0	6·16	
11	Coping over compound wall with laterite brick	R.ft.	0 3 0	280	
12	Cement plastering 1 : 5 compound wall	Sqr.	6 0 0	20·00	
13	Providing jungle wood door ½ panelled and ½ iron barred with hinges, etc., complete	S.ft.	1 8 0	17	
14	Providing and fixing jungle wood door to rear compound wall of Rameswaraswami Temple	,,	1 4 0	25	
15	Blasting rock for forming road way and widening rear of Temple	C.yd.	2 0 0	27	
16	Painting door	L. S.	..	..	
17	Clearing the yard gravelling and consolidating, etc., complete	,,	..	..	
	III. Pendal in front of Sree Rameswara Temple.				
1	Supplying of Balige pole 2½′ girth	R.ft.	0 4 0	150	
2	Carting charges from Agumbe to Tirthahalli	Mile	0 2 6	40	
3	Fixing charges	No.	1 0 0	6	
4	Wire netting 9″ square	S.yd.	0 4 0	60	
5	Painting poles	L. S.	..	..	
	IV. Pakasala (Repairs).				
1	Removing and refixing damaged windows and doors with necessary repairs	S.ft.	0 4 0	42	
2	Flooring with cement concrete and cement plastering with 9″ square cut, etc., complete	Sqr.	18 0 0	2·54	
3	White-washing	,,	0 5 0	16·96	
4	Patch repairs	C.ft.	0 3 6	10	
5	Providing and fixing new ridge tiles in place of broken ones	No.	0 10 0	15	
6	Providing and fixing new Mangalore tiles in place of broker ones	,,	0 2 6	40	
7	Chunam borders over roof	R.ft.	0 4 0	40	
	V. Improving Aswathakatte in front of Madhava Temple.				
1	Dismantling the existing damaged platform	C.ft.	0 0 3	270	
2	Constructing stone retaining wall alround in mud with foundations making use of old available stones	,,	0 2 0	335	
3	Cement pointing	Sqr.	4 0 0	1·80	
4	Slabs over retaining wall	S.ft.	0 6 0	68	
5	Providing steps	No.	8 0 0	1	
6	Other unforeseen charges	L. S.	..	..	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	VI. Repairs to Madhava and Sree Venkataramana Swami Temples.				
1	Dismantling and lowering compound wall	C.ft.	0 0 3	561	
2	Constructing damaged compound wall	,,	0 2 0	28	
3	Coping over laterite brick in mud	R.ft.	0 3 0	140	
4	Cement plastering compound wall	Sqr.	6 0 0	22·20	
5	Clearing the compound yard by removing rank vegetation and levelling, etc.	L. S.	..	..	
6	Constructing steps with parapet, etc., complete ..	,,			
7	Removing the damaged retaining wall and reconstructing to one uniform level with available stones ..	C.ft.	0 2 0	270	
8	Levelling the premises of Venkataramanaswamy temple	C.yd.	0 4 0	50	
9	Blasting rock, etc.	L. S.	..	..	
	VII. Improvements to Bhaga Mantapam.				
1	Excavating foundations	C.yd.	0 4 0	11	
2	Filling in foundations with cement concrete 1:4:8	C.ft.	0 7 0	92	
3	Size stone in mud	,,	0 5 0	188	
4	Burnt stone pillars $1\frac{1}{4}' \times 1\frac{1}{4}'$ roughly dressed including hoisting	R.ft.	2 0 0	54	
5	Burnt stone beams $1' \times 1'$ do	,,	1 12 0	51	
6	Conveying slabs including hoisting and fixing in cement concrete and roughly dressed 6″ thick ..	S.ft.	1 0 0	196	
7	Slabs over retaining wall 6″ thick including roughly dressing and fixing, etc., complete over retaining wall	S.ft.	0 8 0	68	
8	Constructing masonry, Gopuram including cement plastering, cornice, etc., complete	L. S.	..	..	
9	Filling the gaps with size stone in cement mortar ..	C.ft.	0 10 0	30	
10	Cement mortar bund, at the joints	R.ft.	0 3 0	160	
11	Cement pointing to basement	Sqr.	4 0 0	1·82	
12	Unforeseen charges	L. S.	..	..	
	VIII. Miscellaneous Works.				
1	Levelling the acquired area and converting it into garden including enclosing the same with fencing 1 wicket gate and providing seats, etc., complete	L. S.	..	..	
2	Providing, fixing burnt stone slabs paving in the prakaram of Sri Ramaswami Temple	S.ft.	0 4 0	1,150	
3	Repairing the existing damaged stone retaining wall height 3′ to 6′	R.ft.	0 12 0	332	
4	Underpinning and other unforeseen works such as dismantling the damaged portions of covering slabs, etc.	L. S.	..	..	

M. K. RAJAM IYENGAR,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 18th February 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 4th March 1939, for constructing a tunnel on Bharamagiri-Hosdurga Road.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for the above work." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 300 (Rupees three hundred only) in cash or Government Promissory Notes or Mysore Government Bonds, duly